



**Western
Bay of Plenty**
District Council

**Mā tō tātou takiwā
For our District**

**Annual Report to Bay of
Plenty Regional Council**

**Western Comprehensive
Stormwater Annual Report**

67093-DC.01CSC

November 2025

Contents

Introduction.....	3
Monitoring Data Review	5
Microbiological.....	6
Water Clarity	15
Nutrients	22
Metals	31
Hydrocarbons	83
Chemical Oxygen demand.....	86
Water quality field analysis and observations	89
Stormwater Network and Infrastructure Updates	113
Stormwater Mitigation Measures	114
Stormwater Related Incidents	115
Updates to the Asset Register.....	115
New Structures Included in the CSC.....	115

Introduction

Western Bay of Plenty District Council (WBOPDC) holds Resource Consent 67093-DC.01. The purpose of this Resource Consent is to:

- a) Authorise the discharge of stormwater from urban areas within the Western Catchments (refer to condition 2) of the Western Bay District; associated with the resource consents listed in Schedule 1 (as may be updated to include applicable consents which post-date the decision on this CSC); and
- b) To authorise temporary discharges of sediment contaminated stormwater from earthworks related to the replacement of stormwater infrastructure; and
- c) To incorporate existing stormwater discharges associated with the existing resource consents listed in Schedule 1: List of stormwater related consents in the Catchment Management Plans WSZ1, WSZ2 and WSZ3 submitted in support of this application (as updated on 23 January 2020).

The Consent requires monitoring of a range of environmental indicators to assess the quality of stormwater discharges and sediment quality at the upstream, downstream, and stream-channel locations of the receiving environment.

Pursuant to Condition 9.4 of Resource Consent 67093-DC.01, a summary of the monitoring results is to be collated in a report with other Stormwater network information from the reporting year (October to September calendar year).

- 9.4 The consent holder must submit to the Regional Council Chief Executive or delegate an annual report for the Waihi Beach and Katikati catchments, in November of each year, covering:
- a) A summary report of any monitoring undertaken including an analysis of the monitoring results;
 - b) Any stormwater network or stormwater infrastructure upgrade works undertaken;
 - c) Any stormwater induced erosion, flood risk alleviation, or stormwater quality mitigation measures implemented;
 - d) Any incidents resulting in unanticipated contaminants entering the stormwater network, the Investigation of the cause of the incidents and any remedial actions implemented to avoid a repeat occurrence of incident
 - e) An updated Asset Register; and
 - f) Any new structures to be included in the consent (Asset Register)

Table 1. Consent condition specific information.

Consent Condition 9.4	Supporting information (Page no.)
(a) A summary report of any monitoring undertaken including an analysis of the monitoring results;	5
(b) Any stormwater network or stormwater infrastructure upgrade works undertaken	113
(c) Any stormwater induced erosion, flood risk alleviation, or stormwater quality mitigation measures implemented;	114
(d) Any incidents resulting in unanticipated contaminants entering the stormwater network, the Investigation of the cause of the incidents and any remedial actions implemented to avoid a repeat occurrence of incident	115
(e) An updated Asset Register; and	115
(f) Any new structures to be included in the consent (Asset Register)	115

Monitoring Data Review

The following section presents an overview of the monitoring results with a reporting period from 1 October 2024 – 30 September 2025. Specifically, this includes the results for water quality at the five monitoring locations within the catchment (Appendix A). This includes the findings from laboratory analysis and field observations.

The current reporting period includes quarterly baseline samples, 1 baseline remedial sample and 6 rainfall events. While only two rainfall event samples are required annually, due to the locations of these sites and the strict time frame in which the first flush must be collected, these samples have been split up across the monitoring period during various rainfall events to catch the first flush per site.

The trigger values added to each graph (where applicable) only apply to the downstream sites. However, these trigger values have been applied to all graphs to assess whether upstream samples also exceeded these levels.

Overall, the results during this monitoring period demonstrated several water quality trigger value exceedances in the downstream receiving environment, however the majority of these were not consecutive, therefore did not require further action. The exceedance investigation (Appendix C) for the K2 sites is ongoing, as work is occurring with the Dave Hume Pool, upstream of the catchment. The water from the Geothermal bore used at this pool is now being reinjected back into the aquifer rather than being discharged into this stream. The pool is scheduled to officially open in December. Until then, and as shown in this report, the K2 sites have demonstrated consecutive exceedances in E. coli, Dissolved Zinc, Total Zinc and Total Copper.

8.1 Where the quality of receiving waters into which stormwater is discharged exceeds the trigger values listed in Table 1 of Appendix A to this Consent after reasonable mixing, the consent holder must implement the actions identified in Condition 9.2.

9.2 If any water quality trigger value referred to in condition 8.1 is exceeded in three consecutive sampling results for the same site, the consent holder must undertake a contaminant source investigation within 3 months of the third exceedance and submit a report to the Regional Council Chief Executive or delegate.